



Do not scale from this drawing.

•EDINBURGH•
THE CITY OF EDINBURGH COUNCIL

SFN
Sacyr • Farrans • Neopul

Key

Existing Trees/vegetation to be retained

Existing Trees/vegetation to be removed

Existing/Proposed walls

Proposed

Pre-cast concrete flags 450x600x63mm, laid in a staggered bond of 90° to the kerb with 5-10mm joints. Laid in accordance with BS 7533-4*

Calthness natural stone paving flags (castle blend), 450x600x63mm, laid in a staggered bond with 5-10mm joints. Laid in accordance with BS 7533-4, as supplied by BBS (or similar approved)*

Scoutmoor sandstone natural stone paving (diamond sown finish), 450x450x63mm, laid in a staggered bond with 5-10mm joints. Laid in accordance with BS 7533-4 as supplied by BBS (or similar approved)*

Asphalt footpath, to engineers detail

Pedestrian deterring paving: Estahno Grey Granite setts, flamed finish, 200x100mm with deep recessed joints. As supplied by BBS (or similar approved).

Separator strip: width <0.5m Estahno Grey Granite setts, flamed finish 200x100mm with deep recessed joints, width >0.5m paving to match adjacent areas

Cycle route, to engineers detail

Grasscrete: Grassgrid product as supplied by Aggregate Industries (or similar approved), 366x274x100mm

Tactile paving

Ladder tactile paving

Specimen trees: refer to planting schedule and outline specification on sheet 1 for further details

Tree grille (to semi mature trees in hard landscape); Castle grille 1800x1800mm infilled with paving to match surroundings, as supplied by GreenBlue Urban (or similar approved) Orientation of grille to match surrounding paving direction

Linear root barrier: installed for trees in soft adjacent to pavements or utilities, ReRoot1000 as supplied by GreenBlue Urban (or similar approved)

Grass seeding: refer to outline specification on sheet 1

Ornamental shrub/ herbaceous planting: refer to planting schedule and outline specification on sheet 1 for further details

Raised planter: 3mm Cor-Ten steel 2500(0)x950(w)x950(h) as supplied by IOTA (or similar approved)

Cycle stands: galvanised steel 'Sheffield' stands (700-1000mm in length and 750 high), 8no. at each location, as supplied by Braxap (or similar approved)

Litter bin: to match the existing type currently deployed by City of Edinburgh Council within the boundaries of the site

Bench: refer to bench schedule on sheet 1 for further details

Pedestrian wayfinding

ACO Multidrain channel - Please refer to drainage drawings for further details

Kerbs - Please refer to engineers drawings for further details

C01

DD+ UPDATES BASED ON UPDATED ENGINEERING INFO, DRN COMMENTS & ISSUE FOR CONSTRUCTION

SDR

ER

ER

P03

DD+ UPDATES BASED ON UPDATED ENGINEERING INFORMATION AND DRN COMMENTS

SDR

ER

ER

P02

DD+ UPDATES BASED ON DRN AND WORKSHOP COMMENTS AND UPDATED SCHEME ELEMENTS

SDR

ER

ER

Rev.

Date

Description

Drawn

Chkd.

Appd.

Project Title:
EDINBURGH TRAM
YORK PLACE TO NEWHAVEN

Drawing Title:
LANDSCAPE PROPOSALS
DETAILED DESIGN
SHEET 5 OF 15

Scale at A1:
1:500

Status:
FOR CONSTRUCTION

Drawn:
SDR

Checked:
LF

Approved:
ER

Date:
20/03/20

Date:
01/05/20

Date:
01/05/20

Project

Disciplines

Volume

Location

Type

Rate

Number

ETYN-SEF-XXX-XX-DR-L-0020

Subsidiary:
A1

Revision:
C01